

Centrality dependence of the $N(\Omega)/N(\phi)$ ratios and ϕ v_2 - a test of thermalization in Au+Au collisions at RHIC

Sarah-Louise Blyth (for the STAR Collaboration)

Lawrence Berkeley National Laboratory, One Cyclotron Road, Berkeley, California, 94720, USA[‡]

E-mail: slblyth@lbl.gov

Abstract. We present the centrality dependence of the $N(\Omega)/N(\phi)$ ratios and ϕ v_2 measured in Au+Au collisions at $\sqrt{s_{NN}} = 200$ GeV by the STAR experiment at RHIC. The results are compared to measurements of other identified particles and recombination model expectations in order to gain insight into the partonic collectivity and possible thermalization of the produced medium.

1. Introduction

The phenomenon of large baryon/meson ratios of ~ 1 , e.g. for p/π and Λ/K_S^0 , has been observed at intermediate p_T (2-5 GeV/ c) in Au+Au collisions at RHIC [1, 2] and is known as the so-called “baryon anomaly”. It has also been observed that these ratios increase with increasing centrality. The observation of these large ratios prompted the description of particle production at intermediate p_T at RHIC by various quark recombination models [3, 4, 5, 6] which have been successful in qualitatively describing the p_T dependence of the ratios. Measurements of the centrality dependence of the multistrange $N(\Omega)/N(\phi)$ ($sss/s\bar{s}$) ratios can help to provide further insight into particle production mechanisms at intermediate p_T at RHIC.

The ϕ -meson ($s\bar{s}$) is an ideal probe of the properties of the medium produced in nucleus-nucleus collisions at RHIC; with its assumed small interaction cross-section with non-strange hadrons [7] and its relatively long lifetime of 41 fm/ c , which means it mostly decays outside the fireball, it can provide a clean signal, undisturbed by subsequent hadronic interactions, from the early stage of the system’s evolution. The ϕ -meson can also be used to differentiate between mass-type and particle-type effects since it is a meson, but is comparable in mass to the proton and Λ baryon.

Elliptic flow (v_2) is an observable which provides information from the early stages of the collision. At RHIC, the $v_2(p_T)$ of identified hadrons at low p_T (< 2 GeV/ c) has been found to follow a mass ordering consistent with expectations from hydrodynamic

[‡] Current address: Physics Department, University of Cape Town, Rondebosch, South Africa, 7708

models. At intermediate p_T ($2 < p_T < 5$ GeV/ c), identified particle $v_2(p_T)$ has been observed to scale with quark number [8]. This is also consistent with the idea of particle production through quark coalescence and may shed light on the deconfinement of the medium produced in the early stages of relativistic nucleus-nucleus collisions at RHIC. In addition, the multi-strange baryons, Ξ and Ω , have v_2 values comparable to that of the lighter particles which may be evidence for partonic collectivity of the produced medium [9]. Measurements of the centrality dependence of the relatively heavy ϕ -meson can help to differentiate between particle-type and mass effects in $v_2(p_T)$ and provide further insight into the collectivity of the medium.

2. Experiment and Analysis

In these proceedings we present data from Au+Au collisions at $\sqrt{s_{NN}} = 200$ GeV measured by the STAR experiment at RHIC. Approximately 13.5 million minimum bias events and 19 million central-triggered events were analyzed to produce the presented particle ratios and v_2 results. The ϕ -mesons were reconstructed via their decay to two oppositely charged kaons identified by their dE/dx energy loss in the STAR Time Projection Chamber (TPC). The invariant mass distribution was constructed using all combinations of oppositely charged kaons per event and the uncorrelated background was estimated using event-mixing [10]. The resulting ϕ mass peak was then fitted with a Breit-Wigner function (to describe the signal) plus a straight line (to describe the residual background). The $v_2(p_T)$ results were obtained using the v_2 vs. mass method following [11]. The systematic errors in the v_2 include the difference in the results obtained using two different methods and from extracting the raw yields using different fitting criteria.

3. Results

In the left panel of figure 1 we present the centrality dependence of the $N(\Omega)/N(\phi)$ ratios vs. p_T . The Ω spectra used to obtain the ratios were taken from [12] for the central ratio and [13] for the 20-40% and 40-60% centrality ratios. The systematic and statistical errors in the ratios are dominated by the errors in the Ω spectra. Also shown in figure 1 are recombination model calculations for central collisions, where it is expected that the dominant contribution to Ω and ϕ production is from coalescence of thermal s -quarks (TT contribution, dashed line) [14]. For all centralities, at low p_T , the ratios increase monotonically while the “turn-over” points seem to shift towards higher p_T with increasing centrality. This may imply larger thermal s -quark contributions to multistrange hadron production in more central Au+Au collisions at RHIC [14]. The model describes the central data well up to $p_T \sim 4$ GeV/ c after which it overpredicts the ratio. The p_T range 0-4 GeV/ c covers more than 95% of the total yields for the ϕ and Ω and within the framework of the model [14], the majority of the multistrange hadrons are formed through the coalescence of thermal s -quarks in central Au+Au collisions at

RHIC.




Figure 1. Left panel: Centrality dependence of the $N(\Omega)/N(\phi)$ ratios vs. p_T . Recombination model expectations from [14] for central collisions are shown by the dashed (thermal-thermal contribution) and solid lines (sum of all contributions). **Right panel:** Central baryon/meson ratios for Λ/K_S^0 (triangles), p/π (squares), and $N(\Omega)/N(\phi)$ (circles) compared to recombination model expectations by Hwa et al.

The right panel of figure 1 compares the central $N(\Omega)/N(\phi)$ ratio to that for p/π^+ and Λ/K_S^0 and includes recombination model expectations from Hwa et al. [14, 15]. For all cases as a function of p_T , the particle ratios increase, have a turning point at intermediate p_T and then decrease. Also noticeable is a possible shift towards higher p_T in the turning points of the ratios as a function of increasing strangeness content of the particles. This may imply different production mechanisms for strangeness compared to the lighter u and d flavours. For all the particle ratios, the recombination model expects the turning points at higher p_T values than observed in the data.

In the left panel of figure 2, we present the centrality dependence of the ϕ $v_2(p_T)$. The $v_2(p_T)$ values increase with decreasing centrality i.e. with increasing eccentricity of the initial overlap region of the colliding nuclei. This observation is consistent with measurements of other hadrons [16].

The right panel of figure 2 compares the ϕ -meson minimum bias (0-80%) $v_2(p_T)$ to that of Λ and K_S^0 from [8]. The dashed and dash-dotted lines indicate parameterizations based on quark number (NQ) scaling for mesons and baryons respectively [17]. For $p_T < 2$ GeV/c, a mass scaling consistent with hydrodynamic expectations is observed for the ϕ , however higher precision data are needed to allow a final conclusion to be drawn. At intermediate p_T (2-5 GeV/c), the ϕ $v_2(p_T)$ is consistent with that of K_S^0 . This particle type dependence, i.e. baryon/meson dependence of the elliptic flow may imply that the system created in Au+Au collisions at RHIC is in a state of deconfinement before hadronization.




Figure 2. Left panel: Centrality dependence of ϕ $v_2(p_T)$. **Right panel:** Minimum bias ϕ $v_2(p_T)$ (full circles) compared to Λ (open circles) and K_S^0 (squares) and quark number (NQ) scaling parameterizations (lines).

4. Summary

We have presented the centrality dependence of the $N(\Omega)/N(\phi)$ ratios and ϕ -meson $v_2(p_T)$ measured by the STAR experiment in Au+Au collisions at $\sqrt{s_{NN}} = 200$ GeV. The ϕ spectra in central collisions can be described by thermal-type distributions and a recombination model based on coalescence of thermal s -quarks [14] describes the central $N(\Omega)/N(\phi)$ ratio up to $p_T \sim 4$ GeV/c, a range which covers 95% of the yields of these particles. In addition, the $v_2(p_T)$ of the ϕ is consistent with other mesons which implies partonic collectivity of the system in the early stage of Au+Au collisions at RHIC.

References

- [1] B. I. Abelev et al. *Phys. Rev. Lett.*, 97:152301, 2006.
- [2] John Adams et al. nucl-ex/0601042. 2006.
- [3] Denes Molnar and Sergei A. Voloshin. *Phys. Rev. Lett.*, 91:092301, 2003.
- [4] R. J. Fries, B. Muller, C. Nonaka, and S. A. Bass. *Phys. Rev.*, C68:044902, 2003.
- [5] Rudolph C. Hwa and C. B. Yang. *Phys. Rev.*, C67:034902, 2003.
- [6] V. Greco et al. *Phys. Rev. Lett.*, 90:202302, 2003.
- [7] A. Shor. *Phys. Rev. Lett.*, 54:1122–1125, 1985.
- [8] John Adams et al. *Phys. Rev. Lett.*, 92:052302, 2004.
- [9] John Adams et al. *Phys. Rev. Lett.*, 95:122301, 2005.
- [10] John Adams et al. *Phys. Lett.*, B612:181–189, 2005.
- [11] N. Borghini and J. Y. Ollitrault. *Phys. Rev.*, C70:064905, 2004.
- [12] John Adams et al. *Nucl. Phys.*, A757:102–183, 2005.
- [13] John Adams et al. nucl-ex/0606014. 2006.
- [14] Rudolph C. Hwa and C. B. Yang. nucl-th/0602024. 2006.
- [15] Rudolph C. Hwa and C. B. Yang. *Phys. Rev.*, C70:024905, 2004.
- [16] John Adams et al. *Phys. Rev.*, C72:014904, 2005.
- [17] X. Dong, S. Esumi, P. Sorensen, N. Xu, and Z. Xu. *Phys. Lett.*, B597:328–332, 2004.